



TQCI

**Integrating quantum computers
into CEA's TGCC Compute
Center**

04/12/2025

Jean-Marc DUCOS



OUTLINE

- 1. CEA DIF and TGCC presentation**
- 2. TGCC technical infrastructure**
- 3. Specific issues with quantum machine at TGCC services**
- 4. Next step and Feedback**



1 ■ CEA DIF and TGCC presentation



- A first rank research centre in Essonne (south Paris)
 - ~2000 employees, ~100 PhD and postdoctoral students
 - A large usage of HPC resources dedicated to “civilian” (TGCC) or “defence” (TERA-EXA) applications

- Our missions at CEA/DIF
 - French and European research
 - Nuclear warheads design and certification (Simulation Program)
 - Fight against proliferation and terrorism
 - Alert to authorities (geophysical hazards, tsunami, ...)



CEA HPC ressources for Research, Industry and Defence

1 site (CEA/DIF), 2 facilities and 4 computing centres, <https://www-hpc.cea.fr/>



TGCC Facility (open science)


Cold water DLC



Public research
France (GENCI) and Europe (EuroHPC)




Joliot-Curie
22 Petaflop/s
Alice Recoque
1 Exaflop/s 2026



TOPAZE
10 Petaflop/s



CEA and Industrial partners
(CCRT)



TERA-EXA Facility (Defence)

Warm water DLC



CEA/DAM Defence usages
(EXA)

EXA1-HE
180 Petaflop/s

EXA1-HF
36 Petaflop/s



OCRE
R&D Zone



ECRIN
2 Petaflop/s






CEA and Defence partners
(CCMD)

TGCC, a world-class computing centre

➤ Built in 2010 to host and operate large scale supercomputers for HPC




- Computer rooms: 2600 m², technical zone: 3000 m²
- Electrical power capacity: 2x30MW, **36 MW** configured
- DLC capacity: **cold water 10 MW & warm water 20 MW**



GENCI
GRAND EQUIPEMENT NATIONAL DE CALCUL INTENSIF

Jules Verne project (**EuroHPC**),
1+EF HPL, 2026,
TGCC CEA, France

➤ RUBY : Pasqal's quantum simulator system, 100 qubits neutral atoms (Q3/2025)



➤ LUCY : Quandela's photonic quantum system, 12 qubits (Q4/2025)



6 10+-qubit
quantum computers
acquired through a
call for expression of
interest (CEI)

EuroQCS-France
GENCI/CEA

Euro-Q-Exa
LRZ

EuroQCS-Italy
CINECA

30 partners in total

17 countries involved

Lumi-Q
IT4I @ VSB


EuroQCS-Poland
PSNC

EuroQCS-Spain
BSC-CNS




2 ■ TGCC technical infrastructure


Ground floor of the TGCC



Basement of the TGCC



Infrastructure – Electrical power distribution



Infrastructure – Cooling




Seven dry-hybrid cooling towers




Four 3,3 MW chillers



Two 0,5 MW heat pump for heat recovery



Cube Inrow



Direct Liquid Cooling



250 kW Air cooling unit IT room



100 kW Air cooling unit Electrical services room




3 ■ Specific issues with Quantum machine at TGCC services

Power supply

➤ TGCC : Already 3 types of power supply

- Normal
- UPS
- Backup



➤ It's easy to add electrical cabinets as needed for quantum computer

- We currently use supply power (UPS) for quantum computer
- Using backup power is being considered (it was not in the initial specifications)





- TGCC : Direct liquid cooling (85%) and air cooling (15%)
 - Currently a cold water loop at 9°C
- Quantum computer
 - Cold water is available at 9°C (it could be necessary to install a heat exchanger)
 - New air cooling units in the quantum room with flow reversal to prevent dust (from top to bottom)
 - More accurate temperature and humidity control



New hazards for personnel

➤ New risks to be considered

- Laser
- Anoxia
- Pressurized equipment, ...



➤ To tackle these risks, it was necessary to deal with these risks :

- New procedures
- New safety equipment
- Safety files
- Prevention plans, ...



➤ Permission to operate a new facility at the TGCC depends on all of this, and the safety culture is very different between the CEA computing center and the quantum world.



4. ■ Next step and Feedback



- After installing Ruby and Lucy at TGCC, we should soon be welcoming a third quantum computer, based on superconducting cat qubits. This will involve new specifications to take into account :
 - Nitrogen supply management
 - Vibration and acoustic constraints
 - Electromagnetic field constraints, ...

- Feedback from the integration of the first two quantum computers at TGCC :
 - The most difficult point was taking security into account with our level of requirements for an installation in operation at the CEA.
 - The second point of attention is a clear specification of all the needs and constraints for the operation and maintenance of these new quantum computers.



Thank you, questions ?

